



42CrMo-5 TLT Axial Fan Parts Blade Shank Supply Fan Blade Handle M56*2

Our Product Introduction

Basic Information

- Place of Origin: Shanghai
- Brand Name: YIKU
- Model Number: S2GA0863
- Minimum Order Quantity: 1 piece
- Price: negotiable
- Packaging Details: box
- Delivery Time: 2-3month
- Payment Terms: L/C, T/T
- Supply Ability: 100 piece/month



Product Specification

- Name: Blader Shank
- Model: S2GA0863
- Material: 42CrMo-5
- Quantity: 1
- Purpose: Connecting Carriers
- Applicable To: Blower
- Highlight: 42CrMo-5 TLT Axial Fan Parts,
TLT Axial Fan Parts Blade Shank,
M56 Fan Blade Shank

for more products please visit us on axialfanparts.com

Product Description

Blade Shank, Supply fan blade handle M56*2, $\phi 154 \times 401$

技 要求

1.材料需作如下

- (1)同冶 取 作化学成 分析
- (2)同冶 炉同 理取2%,但不少于 套 作机械性能 ($\sigma_b, \sigma_s, \delta, \Psi$)
- (3)同冶 炉同 理取2%,但不少于二套 作冲 (α_k)
- (4) 一件 定硬度(HB)

2.材料 后,机械性能

- (1) $\sigma_b=800 \text{ N/mm}^2$
- (2) $\sigma_s=600 \text{ N/mm}^2$
- (3) $\delta_5=15 \%$
- (4) $\Psi=45 \%$
- (5) $\alpha_k=58 \text{ Nm/cm}^2$
- (6)HB=230~260

3.零件需按JB/T1581-1996作超声波

4.M56×2-6h螺 与螺母配 ,精度不得低于2

5.修 :

- 1)磨 重,必 更 .
- 2) 根部有裂 ,必 更 .
- 3)不能修 螺 ,必 更 .
- 4)叶柄与螺母咬死不能分 气割后,必 更 .

Technical requirement

1. The material shall be tested as follows

- (1) Chemical composition analysis of samples taken with smelting
- (2) 2% of the same continuous heat treatment with the smelting furnace, but not less than two sets of samples for mechanical properties tests ($\sigma_b, \sigma_s, \delta, \Psi$)
- (3) Take 2% of the same continuous heat treatment with the smelting furnace, but not less than two sets of samples for impact test (α_k)
- (4) Determine the hardness of each piece (HB)

2. Material after tempering, mechanical properties

- (1) $\sigma_b=800 \text{ N/mm}^2$
- (2) $\sigma_s=600 \text{ N/mm}^2$
- (3) $\delta_5= 15\%$
- (4) $\Psi= 45\%$
- (5) $\alpha_k = 58 \text{ nm/cm}^2$
- (6) HB=230~260

3. Parts need to be ultrasonic inspected according to JB/T1581-1996

4. M56× 2-6H thread and nut matching, accuracy shall not be less than 2

5. Found during maintenance:

- 1) Serious wear, must be replaced.
- 2) The root of the shaft head is cracked and must be replaced.
- 3) The thread cannot be repaired and must be replaced.
- 4) The petiole and nut bite can not be separated after gas cutting, must be replaced.



Shanghai YIKU Power Equipment Co., Ltd



8613916002258



657925203@qq.com



axialfanparts.com

5587 Dongchuan Road, Pudong New Area, Shanghai